

TOWN OF LEXINGTON

NEW SEWER MAIN LINE INSPECTION POLICY

The Town of Lexington's policy for newly constructed sewer main inspections is the air testing of mains to 5 PSI and hold 5 PSI for 5 minutes, visual inspections of manholes and services, vacuum testing of manholes, and video inspections done on mains using a gradiometer. Any questionable lines may require them to be Mandreled, this will be determined at the discretion of the Town. Provide to the Town, one DVD copy of the inspection.

Sgossett/Word

Engineering/Forms

Approved 11/01/2004 TC